


Do-it-yourself Solar Thermal
Heating Project-
Poquoson, VA
July 2011 – April 2012


Motivation for Project

1. Explore solar technology, benefit from tax incentives
2. Exercise my engineering skills
3. Be productive rather than watching TV
4. Improve comfort while watching TV, etc.

Electric Power Consumption



System Block Diagram*



Radiant Heat System**



Thermal
Reservoir

Solar
Collector
System

*Design from www.BuildItSolar.com. See part list at end of charts.


** Analyzed using Uponor Advanced Design Software

Theory of Control



3D CAD Model- Google SketchUp


Radiant Heat Circuits-
family room, kitchen, laundry room, 1/2 bath



Radiant Heat
Manifold

Reservoir, Circulators
& Controllers

Collector
Panels



Hot Water
Heater
(ref only)

Solar Collector Installation-

15° East of True South, 15° Elevation* from Horizontal



Before



After

*vertical orientation maximizes collection in winter, minimizes in summer when unused

Reservoir Installation in Garage

- 250 gal of tap water
- Vented to atmosphere



Before



After

Radiant Heat Distribution Manifold Installation in Coat Closet




Manifold Shutoff
Valves, 2 places

Circuit Flow
Adjustors


Pressure
Pump for
initial leak
check only

Radiant Heat Installation:


610 sq ft: 2 Loops in Family Room, 1 in Kitchen, 1 in laundry room / bathroom



Joist Trak plates for 1/2" PEX tubing
















Operator Interfaces




Project Management

- 9 month duration
- \$6,565 material costs
- 288 man-hours,
 - Essentially by a single worker
 - Online research time was significant, but is not included

Timeline of Project

Task description	Jun-11	Jul-11	Aug-11	Sep-11	Oct-11	Nov-11	Dec-11	Jan-12	Feb-12	Mar-12	Apr-12
Go ahead decision											
Install Radiant Heat System											
rmv underfloor insulation. Instl band joist insul, diffuser plates, pex pipe, manifold, 6" underfloor insul											
Fab & Install H2O Reservoir in garage											
Fab copper pipe grid assys for collectors											
Fab circulator panel assy, instl lines to Rad Heat manifold											
Fab collector assys											
Instl collectors, lines to reservoir											
1st water thru Collectors & Rad Heat Sys											
Insulate collector lines. Instl lid on reservoir											

Cost of Materials = \$6,565



Manhours

- 4 hrs / day worked, over 73 work days, by a single workman
- Band joist insul = 12.0 hrs for 95.5 linear ft = 8 linear ft / hr
- Rad heat instl = 73.9 hrs for 610 sq ft = 8.3 sq ft / hr
- Instl Manifold Feed Lines = 13.0 hrs
- Fab collector assemblies = 59.2 hrs = 19.7 hrs / assy
- Installation collector assemblies = 35.8 hrs = 11.9 hrs / instl
- Fab Reservoir = 20.7 hrs
- Fab Circulator Pallet = 42.0 hrs
- Collector Plumbing = 19.1 hrs


Total labor = 288 man-hrs

Performance of System:

- Predicted performance of Collectors and Radiant Heat System
- Data collection
- Analysis
 - Collection efficiency: overall, seasonal
 - Heating of house
 - Cost recovery
 - Reliability and Maintainability

Solar Obscuration Measurements

June 2011, 5' above ridgeline of garage roof, x = 4' out from 2nd story wall



Trees on
Property
Line

Our Trees


Neighbor's
Tree

Predicted Energy Gathering

from comparable commercial collector

Norfolk Intl Airport, Viessman Vitosol 200F Power Output vs. Season
Moving Average of Previous 10 days,
T in=113F, T out=122F, Collector Az=-15 deg, Collector Elev=75deg,
1991-2005 Average = 442 BTU/sq ft/day

For three 4'x8' collectors = 42,432 BTU/day




Predicted Heating Performance


- Calculated using free Advanced Design Suite software from Uponor
 - 68°F room temp, 24°F outdoor temp, 23 mph wind
 - 630 sq ft, average construction, $T_{in}-T_{out} \leq 10^\circ$
 - 7,540 BTU/hr required = 1.8 gal/min @ 109°F
- Given predicted collector performance of 42,432 BTU/day, we'll get 5.6 hrs of 68°F room temp each day.
- Existing heat pump runs in parallel.
 - Solar heat setpoint 2° above heat pump to draw from solar first
 - Degree of interaction unknown

Data Acquisition System

- Solely for initial testing, the removed
- Arduino based data logger
 - Real Time Clock for time stamping
 - SD Card Reader module for data storage
 - Cost approximately \$60
- Dataset includes
 - Temp of room
 - Temp of H2O in Reservoir
 - Outdoor Temp
 - Temp in Garage
 - Insolation on Collectors
 - Radiant Heat Status (ON/OFF)
 - Time of day



Design Flaw = Freeze Up



- 23 Jan 2013 Overnight temp = 18 deg F
- Eastern & western collectors froze & split pipes. No leak in center collector.
- Pumped tank dry

Measured Collector Performance

- No heat draw from Reservoir (Rad ht OFF)
- Measure on cloudless days, no leaves on trees
- Heat gain = (Temp rise of tank) x (vol tank) x (density water) x (heat capacity of water)

12 March 2012:

$$\begin{aligned} \text{Heat Gain} &= (100^\circ - 74^\circ) \times (250 \text{ gal}) \times (62 \text{ lb/cu ft}) \times (1 \text{ BTU/lb/}^\circ\text{F}) \\ &= 48,360 \text{ BTUs / day} = \underline{\underline{504 \text{ BTU / sq ft / day}}} \end{aligned}$$

9 Nov 2012: 510 BTU / sq ft / day

vs. predicted avg of 450 BTU / sq ft / day. *Pretty Good!*

Measured Heating Performance

- Works well in spring and fall- no heat pump at all!
- Unclear about winter. Interaction w/ heat pump unclear, still figuring out ramp-up / down times
- Added set-back timer to heat rooms only in afternoon & evening
- With reservoir temp around 120°F, loses ~6° / night with unheated garage @ 50°

Was Project Successful?

- ✓ 1. *Explore solar technology, benefit from tax incentives*
 - Learned much about solar technology, only got minimal tax break for insulating floor
- ✓ 2. *Exercise my engineering skills*
 - YES! Design / build / test of plumbing, electrical, carpentry, controls, data logging
- ✓ 3. *Be productive rather than watching TV*
 - Yes. Watched little TV during the project
- ✓ 4. *Improve comfort while watching TV, etc.*
 - Yes. Den / kitchen was 60-62°F in winter, now 66-68°F

Items in Block Diagram

<u>Item #</u>	<u>Description</u>	<u>Make</u>	<u>Model</u>	<u>Cost</u>
1	Solar Collector	self	self	\$ 483.00
2	Tubing	PEX	3/4 diam	\$ 0.46
3	Pump, Collector	Taco	009-SF5	\$ 326.00
4	Sensor, Coll'r Temp	incl w/ Steca	-	-
5	Water	God	Tap	-
6	Tubing	PEX	3/4 diam	\$ 0.46
7	Tubing	PEX	3/4 diam	\$ 0.46
8	Valve, Mixing	Honeywell	AM101-US-1	\$ 75.00
9	Pump Rad Ht	Grundfos	UP15-29SF	\$ 164.00
10	Manifold, Supply	RHT	FN5-4-90	\$ 129.00
11	Manifold, Return	incl w/ supply mfld	-	-
12	Rad Ht Loop	PEX & Joist Track	1/2 diam	\$0.89 / ft
13	T'stat, Tank	Johnson Controls	A419ABC-1C	\$ 56.75
14	T'stat, Room	Johnson Controls	A419ABC-1C	\$ 56.75
15	Controller, Collector	Steca/Solene	TR 0301 U	\$ 187.00
16	Sensor, Tank Temp	incl w/ Steca	-	-
17	Sensor, Room Temp	?	RTD, 1000Ω	\$ 10.00
18	Sensor, Tank Temp	?	RTD, 1000Ω	\$ 10.00
19	Valve, Flow Cntl	incl w/ supply mfld	-	-
20	Timer, Temp Setback	Amazon.com	7 day	\$ 20.00